



SECTION @ FASCIA
SCALE: NONE

A
CA-3




SECTION @ COLUMN
SCALE: NONE

C
CA-3




DETAIL "1"

FOR BID ONLY



SECTION @ FASCIA
SCALE: NONE

B
CA-3



DETAIL "2"

TAPE APPLICATION NOTE:	
(1)	BOTH SURFACES TO BE TAPED MUST BE WIPED CLEAN W/50/50 SOLUTION ISOPROPAL ALCOHOL AND WATER.
(2)	WIPE ALL SURFACES DRY.
(3)	SQUEEGEE TAPE ONTO METAL STRIP APPLYING 15 PSI.
(4)	ROLL FINISHED JOINT APPLYING MINIMUM PRESSURE OF 15 PSI.
(5)	50 PERCENT BOND STRENGTH WILL BE ACHIEVED AFTER 20 MINUTES. FULL BOND STRENGTH WILL BE ACHIEVED AFTER 72 HOURS.

DESIGN LOADS:
 DEAD LOAD = 3 p.s.f.(DECK + LIGHTS) +
 WEIGHT OF STRUCTURAL COMPONENTS
 LIVE LOAD = 20 p.s.f.
 SNOW LOAD = 20 p.s.f.
 WIND LOAD = 90 m.p.h. EXP. C
 BLDG CODE = 2009 NEW MEXICO COMMERCIAL BUILDING CODE
 EQUIVALENT LATERAL FORCE PROCEDURE
 LATERAL FORCE RESISTING SYSTEM = CANTILEVERED
 COLUMN SYSTEM-ORDINARY STEEL MOMENT FRAME
 SITE CLASS = D
 Ss (0.2) = 0.57
 S1 (1.0) = 0.17
 SDS = 0.512
 SD1 = 0.241
 Fa = 1.34
 Fv = 2.12
 R = 1.25
 IMPORTANCE FACTOR = 1.0
 OCCUPANCY CATEGORY = II
 SEISMIC DESIGN CATEGORY = D
 CS = 0.410
 CONSTRUCTION TYPE = IIB
 OCCUPANCY CATEGORY = M
 TOTAL SEISMIC BASE SHEAR BOTH DIRECTIONS = 15.24 KIPS

LANE SUPPLY, INC.
 120 FAIRVIEW
 ARLINGTON, TX. 76010
 (817) 261-9116

SEAL
 RICHARD D. MCCORMICK
 NEW MEXICO
 15645
 PROFESSIONAL ENGINEER
 FEB 1-2 2015

NO.	DATE	REVISIONS	CHK'D
1	2/13/2015	PERMIT SET	CP

LSC: 53703
 DRAWN BY: CP
 CHECKED BY: CP
 DATE: 2/4/2015

CIRCLE K STORES INC.
 CIRCLE K
 S.E.C. COORS BLVD. & GUN CLUB RD. S.W.
 ALBUQUERQUE, NM
 42'-10" X 118'-2" CANOPY

CA-4