[illegible]

LSC:	53703
DRAWN BY:	CP
CHECKED BY:	
DATE:	2/4/2015

CIRCLE K STORES INC.  
CIRCLE K  
S.E.C. COORS BLVD. S.W. & GUN CLUB RD. S.W.  
ALBUQUERQUE, NM  
42'-10" X 118'-2" CANOPY

CA-2



YOUT  
JE

1 1/2"  $\phi$  A307  
THREADED ROD

2 HEX NUTS

PL 3/4" x 5" x 5"

The diagram shows a vertical threaded rod passing through a horizontal plate. Two hex nuts are shown on the rod, one above and one below the plate. A leader line points from the text 'YOUT' and 'JE' to a circle containing two horizontal lines, representing a nut and washer. Another leader line points from the text '1 1/2"  $\phi$  A307 THREADED ROD' to the rod. A third leader line points from the text '2 HEX NUTS' to the two nuts. A fourth leader line points from the text 'PL 3/4" x 5" x 5"' to the horizontal plate.

**FOR BID ONLY**


FOUNDATION NOTES:

GENERAL NOTES:

1. ALL FOUNDATION WORK BY OTHERS AND SUBJECT TO LOCAL APPROVAL.
2. THE FOUNDATION DESIGN IS BASED UPON SECTION 1807.3.2.2—NEW MEXICO COMMERCIAL BUILDING CODE 2009 EDITION. THE DESIGN CRITERIA IS BASED ON SOILS REPORT BY: TERRACON CONSULTANTS, INC. TERRACON PROJECT NO. 66145048  
DATED: SEPTEMBER 5, 2014: SITE CLASS D, SOIL BEARING CAPACITY OF 2500 p.s.f. AND A PASSIVE SOIL PRESSURE OF 300 p.s.f. PER FOOT OF DEPTH.
3. DRILLED SHAFT FOOTINGS SHALL BE INSTALLED PER ACI STD. 336.
4. CONCRETE DESIGN AND CONSTRUCTION SHALL CONFORM TO ACI STANDARD 318-08 "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE."
5. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE (F'C) AT THE END OF 28 DAYS SHALL BE 2500 PSI MIN.
6. REINFORCING STEEL SHALL BE GRADE 60 AND CONFORM TO ASTM A615 LATEST REVISION.
7. DETAILING, FABRICATION AND PLACEMENT OF REINFORCING BARS SHALL COMPLY WITH ACI 315, ACI 318 AND CRSI STANDARDS.
8. ANCHOR BOLTS SHALL CONFORM TO ASTM A307.
9. LANE IS NOT RESPONSIBLE FOR FOOTING POURED PRIOR TO PERMITTING.
10. FOOTING ARE DESIGNED TO BE CONSTRAINED AT THE TOP BY A 6" SLAB. IF THEY ARE NOT, PLEASE NOTIFY LANE SUPPLY CO.
11. POUR FOOTINGS TO SAME TOP ELEVATION.
12. USE MASTER FLOW 928 NON-SHRINK GROUT OR EQUIVALENT  
F'm=5000 p.s.i.

1. TOP OF ALL CANOPY FOOTINGS ARE TO BE POURED A MINIMUM OF 12" BELOW FINISHED GRADE OR AS REQUIRED BY LOCAL CODES AND ORDINANCES.
2. IT IS THE OWNERS RESPONSIBILITY TO CONVEY TO ALL CONTRACTORS THAT IT IS THEIR RESPONSIBILITY TO INSURE THAT THE SITE IS PROPERLY EXCAVATED AND GRADED. DURING CONCRETE FORMING PRIOR TO AND AFTER THE POUR, THE CONCRETE SHOULD BE CHECKED FOR PROPER ELEVATION, SQUARE AND CORRECT DIMENSIONS.
3. MEASUREMENTS FOR ANCHOR BOLTS ARE EXACT AND SHOULD BE RECHECKED TO INSURE PROPER LOCATION.
4. CORRECTION OF LOCATION, OF ELEVATION AND OF DIMENSIONAL ERRORS MUST BE MADE PRIOR TO THE ARRIVAL OF THE ERECTION CREW AND PRIOR TO THE ERECTION OF THE STRUCTURE.
5. AFTER THE FORMS HAVE BEEN REMOVED, ALL TRENCHES, HOLES AND UNEVEN SITE CONDITIONS MUST BE LEVELED TO INSURE A SAFE WORKING AND ACCESS AREA ACCEPTABLE TO LOCAL, STATE, FEDERAL AND OSHA AGENCIES.

*VERY IMPORTANT:*



\* MUST PROVIDE THIS INFORMATION.

## DESIGN LOADS:

DEAD LOAD = 3 p.s.f.(DECK + LIGHTS) +  
WEIGHT OF STRUCTURAL COMPONENTS  
LIVE LOAD = 20 p.s.f.  
SNOW LOAD = 20 p.s.f.  
WIND LOAD = 90 m.p.h. EXP. C  
BLDG CODE = 2009 NEW MEXICO COMMERCIAL BUILDING CODE  
EQUIVALENT LATERAL FORCE PROCEDURE  
LATERAL FORCE RESISTING SYSTEM = CANTILEVERED  
COLUMN SYSTEM-ORDINARY STEEL MOMENT FRAME  
SITE CLASS = D  
Ss (0.2) = 0.57  
S1 (1.0) = 0.17  
SDS = 0.512  
SD1 = 0.241  
Fa = 1.34  
Fv = 2.12  
R = 1.25  
IMPORTANCE FACTOR = 1.0  
OCCUPANCY CATEGORY = II  
SEISMIC DESIGN CATEGORY = D  
CS = 0.410  
CONSTRUCTION TYPE = IIB  
OCCUPANCY CATEGORY = M  
TOTAL SEISMIC BASE SHEAR BOTH DIRECTIONS = 15.24 KIPS