



Circle K Southwest Prototype 4480 - 08/17/2013
D
C
B
A
Drawing Name: P:\2014\20140041.5\2014 Electrical Construction Documents\Drawings\Current\20140041.5.11.dwg User: latonia.williams Date: 08/28/2014 Time: 10:00am Plot on: 08/28/2014 Time: 10:00am Plot by: mls



2 CANOPY LIGHTING PLAN
SCALE: 3/32" = 1'-0"

1 ELECTRICAL SITE PLAN
SCALE: 1" = 20'-0"



3 POLE BASE DETAIL
NOT TO SCALE

GENERAL NOTES

1. ALL EXTERIOR DEVICES TO BE WEATHERPROOF.
2. ALL FUEL ISLAND CONDUITS SHALL BE ROUTED TO THE RESPECTIVE PANELS AND/OR TO THE FUEL CONTROL PANELS LOCATED IN THE MANAGERS OFFICE/STORAGE ROOM.
3. PROVIDE ALL EMPTY CONDUITS WITH PULL STRING AND CAP AT BOTH ENDS.
4. ELECTRICAL CONTRACTOR SHALL CONTACT POWER COMPANY REGARDING EXACT LOCATION OF ALL PRIMARY SERVICE EQUIPMENT, TRENCH LOCATIONS, TRANSFORMER LOCATION, METER LOCATION, ETC.
5. ELECTRICAL CONTRACTOR SHALL PROVIDE NECESSARY SECONDARY CONDUITS, POWER TRENCHING, BACKFILL, CONCRETE PADS FOR TRANSFORMERS AND SERVICE EQUIPMENT AND CONDUIT STUBS INTO TRENCH AS REQUIRED BY POWER COMPANY AND TO THEIR SPECIFICATIONS.
6. ELECTRICAL CONTRACTOR SHALL CONTACT TELEPHONE COMPANY REGARDING EXACT LOCATION OF ALL PRIMARY SERVICE EQUIPMENT, SERVICE EQUIPMENT, TRENCH LOCATIONS, ETC.
7. ELECTRICAL CONTRACTOR SHALL PROVIDE ALL NECESSARY TELEPHONE TRENCHING, BACKFILL, AND CONDUIT STUBS INTO TRENCH AS REQUIRED BY TELEPHONE COMPANY AND TO THEIR SPECIFICATIONS.
8. ALL WIRING OUTSIDE SHALL BE A MINIMUM OF #10 COPPER WITH TYPE 'XHHW-2' INSULATION. FOR UNDERGROUND CIRCUITS RUN IN P.V.C., PROVIDE A #10 COPPER BOND IN ADDITION TO CIRCUIT CONDUCTORS.
9. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR COORDINATION AND COMPLIANCE WITH THE UTILITY COMPANY'S REQUIREMENTS. WITHIN TWO WEEKS AFTER AWARD OF CONTRACT, SUBMIT (2) COMPLETE SETS OF PLANS, INCLUDING PLOT OF SURVEY, TO UTILITY COMPANY FOR COORDINATING. ROUTING OF INCOMING POWER AND TELEPHONE SERVICE SHOWN ARE FOR ESTIMATING PURPOSES ONLY. ACTUAL ROUTING, CONDUIT, TRENCH, AND PAD REQUIREMENTS SHALL BE AS SPECIFIED BY THE UTILITY COMPANY. CONFIRM ALL REQUIREMENTS WITH UTILITIES PRIOR TO INSTALLATION.
10. ALL UNDERGROUND CABLE, PIPE, AND CONDUITS SHALL BE DETECTABLE (METALLIC) OR HAVE A DETECTABLE UNDERGROUND DEVICE INSTALLED PER AZ STATUTE 40-360.22.M.
11. ALL EXTERIOR LIGHTING SHALL BE FULL CUT OFF AND HORIZONTALLY TO THE GROUND.

KEY NOTES

- 1 3/4" CONDUIT FOR TANK MONITOR CONTROL.
- 2 3/4" CONDUIT FOR VR SENSOR CONTROL. PULL AND TERMINATE VEEDER ROOT WIRING AT PUMPS, AUTO TANK GAUGES, BRINE SENSORS, HOOK SWITCHES AND TSS350. PROVIDE BELDEN 8860 OR EQUIV. 18-2 STRANDED, OAS, JACKETED, PLENUM CABLE. VERIFY/ COORDINATE WITH FUEL PIPING PLANS.
- 3 3/4" CONDUIT TO EQUIPMENT ROOM FOR INTERCOM. PULL AND TERMINATE INTERCOM WIRING. 22/2 STRANDED, OAS, JACKETED, PLENUM CABLE. VERIFY/ COORDINATE WITH FUEL PIPING PLANS.
- 4 3/4" EMPTY CONDUIT - (EXTRA).
- 5 PROVIDE SEAL OFF FITTINGS AT EACH END OF CONDUIT IN CONJUNCTION WITH G.V.R. DISPENSER MANUAL.
- 6 WP J-BOX FOR POLE SIGN, VERIFY EXACT LOCATION WITH OWNER. (INSTALLED UNDER SEPARATE PERMIT)
- 7 1" CONDUIT FOR POWER HOMERUN.
- 8 SERVICE ENTRANCE SECTION.
- 9 (3) 4" EMPTY CONDUITS FOR SECONDARY FEEDERS.
- 10 PROVIDE HOUSEKEEPING PAD FOR POWER CO. PAD MOUNTED TRANSFORMER PER SERVING POWER COMPANY REQUIREMENTS.
- 11 (2) 4" CONDUITS FOR SERVING POWER CO. PRIMARIES.
- 12 TERMINATE PER SERVING UTILITY CO. REQUIREMENTS.
- 13 (3) 4" EMPTY CONDUITS FOR TELEPHONE SERVICE. VERIFY EXACT QUANTITY AND SIZE WITH SERVING TELEPHONE COMPANY.
- 14 "EMERGENCY POWER OFF" SWITCH PER NEC 2008, NEC ART 514.11. PROVIDE SIGNAGE PER IFC SECTION 2204, 2205. (VERIFY EXACT LOCATION WITH CIRCLE 'K').
- 15 WP J-BOX FOR COMPLETE CONNECTION OF CANOPY SIGN. VERIFY EXACT LOCATION IN FIELD.
- 16 WP J-BOX FOR COMPLETE CONNECTION OF WATER/AIR FILL STATION. VERIFY EXACT LOCATION IN FIELD, AND VERIFY REQUIREMENTS PRIOR TO ROUGH-IN.
- 17 1" C CONDUIT FROM ELECTRICAL ROOM/MECHANICAL ROOM, TO CLOSEST CANOPY COLUMN. ROUTE UP TO CANOPY DECK FOR SPEAKER CONNECTION.
- 18 NOT USED.
- 19 NOT USED.
- 20 LIGHTING CIRCUITS SHALL BE ROUTED VIA 20A 12 POLE ELECTRICALLY HELD LIGHTING CONTACTOR CONTROLLED BY THE 'EPO' SWITCH LOCATED ON THE GAS CANOPY. SEE DETAIL 1 SHEET E1.5.
- 21 VENT RISER FROM TANKS.
- 22 COORDINATE WITH CIVIL DRAWINGS.
- 23 TANK FILL POINT.
- 24 3/4" CONDUIT FROM GAS CANOPY TO ELECTRICAL RM FOR MUSIC/SPEAKERS


GreenbergFarrow

19000 MacArthur Blvd., Suite 250
Irvine, CA 92612
t: 949 296 0450 f: 949 296 0437

COPYRIGHT NOTICE
This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional

ISSUE/REVISION RECORD	
DATE	DESCRIPTION
02/28/2014	PERMIT/BID SET

PROFESSIONAL SEAL



PROFESSIONAL IN CHARGE
GUIDO INGA-ALVAREZ
PROJECT MANAGER
JOHN ADDISON
QUALITY CONTROL
GUIDO INGA-ALVAREZ
DRAWN BY
LATONYA WILLIAMS

PROJECT NAME
CIRCLE K STORES, INC.

PFLUGERVILLE TEXAS

SEC WEST PECAN ST. & SARAH'S CREEK DR. PFLUGERVILLE, TX



PROJECT NUMBER
20140041.5

SHEET TITLE
ELECTRICAL SITE PLAN

SHEET NUMBER
E1.1