












DRAWING NUMBER: P:\1514\20140041.5\200 Standard Construction Documents\Drawings\Current\20140041.5.dwg and Modified: File 2014 - 7/1/2014 Modified on: File 2014 - 8/1/2014 - 8/1/2014 by: JWB


D

C

B

A

LIGHTING FIXTURE SCHEDULE							
TYPE	MANUFACTURER CATALOG NO.	LAMP QTY. & TYPE	FIXTURE WATTAGE	VOLTS	DESCRIPTION	MOUNT HEIGHT	REMARKS
	CREE CR24-40L-40K-S-HD	(1)LED	33	120	2X4 FLUORESCENT TROFFER, 12 CELL PARABOLIC ELECTRONIC BALLAST	RECESSED IN CEILING -	- -
	CREE CR24-40L-40K-S-HD-EB14	(1)LED	33	120	2X4 FLUORESCENT TROFFER, 12 CELL PARABOLIC ELECTRONIC BALLAST, WITH EMERGENCY BACKUP	RECESSED IN CEILING -	PROVIDE 90 MINUTE BATTERY BACK-UP BALLASTS 1200 LUMMENS MIN.
	CREE CR24-40L-40K-S-HD	(1)LED	33	120	2X4 FLUORESCENT TROFFER, 12 CELL PARABOLIC ELECTRONIC BALLAST	RECESSED IN CEILING -	- -
	CREE CR24-40L-40K-S-HD-EB14	(1)LED	33	120	2X4 FLUORESCENT TROFFER, 12 CELL PARABOLIC ELECTRONIC BALLAST, WITH EMERGENCY BACKUP	RECESSED IN CEILING -	PROVIDE 90 MINUTE BATTERY BACK-UP BALLASTS 1200 LUMMENS MIN.
	CREE LR6-10L-35K-120V-A-DR-GU24	(1) RR6-12W-GU24 LED	11	120	6" LED7 DOWNLIGHT FIXTURE	RECESSED IN CEILING -	- -
	CREE WS4-59L-40K-10V-FD	(1)LED	63	120	WALK-IN COOLER LIGHT FIXTURE	- -	COOLER RATED -
	NOT USED.						
	E-CONOLIGHT E-KNB1EK	(8)LM16-50-30K-25-D	35	120	TRACK MOUNTED LED FIXTURE	- -	- -
L	CREE LR6C-10L-35K-120V-A-DR-GU24	(1)LED	11	120	ATTACHED CANOPY DOWNLIGHT	RECESSED IN SOFFIT	6" DIAMETER STANDARD
SEC	CREE SEC-EDG-4M-WM-04-D-UL-SV-700	(1)LED	17	120	EXTERIOR BUILDING WALL MOUNTED SCONCE	SEE ARCHITECTURAL	WITH ARCHITECT/OWNER -
A40-SL (CAN)	BETA LED # CAN-304-SL-RS-04-C-UL-WH-525-43K	(40) LEDs	68	120	CANOPY LIGHTING WITH FLAT LENS NON-DIRECTIONAL	RECESSED IN CELING OF CANOPY	VERIFY COLOR AND FINISH WITH ARCHITECT/OWNER -
B06 (A)	BETA LED # STR-LWY-4M-HT-06-D-UL-SV-700-43K	(60) LEDs	139	120	SINGLE HEAD POLE MOUNTED EXTERIOR FIXTURE	MOUNTED ON 20'-0" POLE -	VERIFY COLOR AND FINISH WITH ARCHITECT/OWNER
B08 (C)	BETA LED # STR-LWY-3M-HT-08-D-UL-525-43K	(80) LEDs	278	120	DUAL HEAD POLE MOUNTED EXTERIOR FIXTURE 90 DEGREE MOUNT ARM	MOUNTED ON 20'-0" POLE	VERIFY COLOR AND FINISH WITH ARCHITECT/OWNER -
	DUAL LITE LZ20NI	WITH FIXTURE	-	120	EMERGENCY FIXTURE (2) HEAD	8'-0" A.F.F. WALL MOUNT	WITH 90 MIN. BATTERY BACK-UP -
	DUAL LITE LXURWEI	WITH FIXTURE	-	120	EXIT SIGN WIRE AHEAD OF LOCAL SWITCH	- -	WITH 90 MIN. BATTERY BACK-UP -
	HBA	-	-	120	DUAL TECHNOLOGY CEILING MOUNTED OCCUPANCY SENSOR (SOUND & MOTION)	CEILING -	- -



 **LIGHTING CONTROL DIAGRAM**
Scale: N.T.S.

